



Andrew Kressly  
Maintenance & Grounds Supervisor  
195 SW 3<sup>rd</sup> Ave. • Ontario, Oregon 97914  
Phone 541.709.6252 • Fax 541.889.8553  
akressly@ontario.k12.or.us

April 7, 2022

## REQUEST FOR PRICING

### Summary Overview:

The Ontario School District is requesting **Labor only** pricing for the installation of:

2,460' of 5' tall chain link fence

175' of 4' tall chain link fence

2,500' of Fenceguard product

(Will include page on how to install Fenceguard material)

This is a Labor only request as we have materials on hand ready to install.

The installation will include the following:

2' deep by 6" diameter holes on line posts, 8" diameter on end posts

10' spacing on posts

Tension wire along the bottom of mesh

Dirt hauled away from post holes

Installation of gates and rolling gates (will provide locations as where to be installed)

See attached pictures

We will provide water for concrete mixing

Line posts, end posts, top rail and all fittings to complete the install

Installation of the Fenceguard material

160' of the 5' fence will be installed into asphalt, there used to be existing fence, so some concrete and poles may need removed

160' of privacy slats installed in the 5' fence

No open holes overnight or they would need to be covered as to prevent fall ins

District will move sprinklers before work begins

For any questions regarding this RFP, contact Andrew Kressly, Maintenance & Grounds Supervisor, at (541) 709-6252, or by email [akressly@ontario.k12.or.us](mailto:akressly@ontario.k12.or.us).

**RFP Submission:** RFP's received after April 15<sup>th</sup>, 2022 at 12:00 PM will not be considered.

RFP's may be submitted by mail, addressed: **195 SW 3<sup>rd</sup> Ave, Ontario, OR 97914**, attn: Andrew Kressly, RFP's may also be submitted by email to [akressly@ontario.k12.or.us](mailto:akressly@ontario.k12.or.us). RFP's must be clearly labeled "**Chain Link Fence Installation**" and include submitter contact information. Submissions must include all required information.

**Award:**

Award of this project will be based on the lowest overall price, earliest start date, prior experience with the Ontario School District, and local or in-state business. (Contractors shall include in their submission a proposed timeline.)

**OTHER REQUIREMENTS**

Prevailing Wage – If the combined price of the Project exceeds fifty thousand dollars, the Prevailing Wage must be factored into the bid, and shall be the responsibility of the Contractor.

Oregon CCB – The Contractor shall provide proof of Oregon CCB License, and provide current Oregon CCB number.

Insurance – The Contractor shall provide proof of Insurance and Worker's Compensation Insurance.

OSHA – The Contractor is responsible for following all OSHA guidelines relating to the work for the Project. *Students and staff may be present at the time of work for the Project; safe zones will need to be established in areas around the work site.*

Responsibility of the District – Ontario School District will mark where fencing will be installed and call Dig Line prior to the project start date. Responsibilities of the Ontario School District *must be clearly stated in the RFP.*

Timeline – The Contractor shall provide a Project Timeline and a Date of Completion for the Project. *All fencing must be installed and billed out prior to September 15<sup>th</sup>, 2022.*

Vehicles and/or Equipment – If school is in session, Contractor vehicles and any equipment must be kept out of student loading/unloading zones.

Tobacco Use – Oregon schools are considered a tobacco free zone; any workers using tobacco products will have to leave school property while using tobacco products.

Background Checks – The District requires all individuals working on school grounds to complete a Background Check and Fingerprinting. See **Attachment: Background Checks**. *If you have done work for the District and completed a background check in the last year, your previous background check may still be sufficient; contact the District Office at 541-889-5374.*

## INSTALLATION PROCESS

**FENCEGUARD™ IS INSTALLED ON NEW FENCING OR EXISTING FENCING WITH AT LEAST ½ INCH OF CLEARANCE.**



*FenceGuard™* provides "channel" for fencing fabric and proper alignment. The "offset" side should be on the same side of post as the chain link fabric. Two panels per section of fencing.


*FenceGuard™* panels overlap at post locations and within the section between posts. Clamp overlapping panels during installation to provide proper alignment of panels. 3-inch notches for round posts.



Drill 3/16" holes for rivets at overlap of *FenceGuard™* panels at post locations (not at overlap between posts) to allow expansion/contraction to occur and to avoid buckling. When pieces are installed at corners (i.e. 90°), use hole saws at diameter of corner post size and create new holes far enough from end of panel to create clean corners. Cut *FenceGuard™* sections as necessary to splice panels together. Terminal posts can be capped with *FenceGuard™* by cutting another panel to reasonable length and securing to post with rivets.

Maintain fence line by mowing over the edge of the panels. Seasonal recommendation to use flat blade tool to slide underneath panels and skim along each side to create a new clean line.





Imagery ©2022 Maxar Technologies, Map data ©2022 20 ft

Measure distance  
Total distance: 157.64 ft (48.05 m)

Google Maps 5 Chain Link, no gates, Britano Middle School, 573 SW 2nd Ave



Imagery ©2022 Maxar Technologies, State of Oregon, Map data ©2022 Google 50 ft

Measure distance  
Total distance: 535.63 ft (163.26 m)

Google Maps 4 Chain Link 1-12 Rolling gate installed 20' from north fence, Alken Elementary 1297 W Idaho Ave




Imagery ©2022 Maxar Technologies, State of Oregon, Map data ©2022 20 ft

Measure distance  
Total distance: 49.78 ft (15.17 m)



Measure distance  
Total distance: 179.21 ft (39.38 m)





Measure distance  
Total distance: 212.66 ft (64.82 m)



Measure distance  
Total distance: 1,532.35 ft (467.06 m)

## **ATTACHMENT: BACKGROUND CHECKS**

The cost to complete the criminal history check is: **\$59.00 + \$12.50** (paid online upon registration by employee). Below is the Fieldprint information needed to complete background checks.

### **FINGERPRINT INFORMATION**

#### **ONTARIO FIELDPRINT OFFICE**

Smith's Pack & Ship  
251 W Idaho Avenue  
Phone: 541-889-7690

Cost: \$12.50 (due at the time appointment is scheduled)

Fee may be paid with credit card or electronic check by providing routing and account information. NOTE: If you do not show for your scheduled appointment, or you cancel or reschedule your appointment within 24 hours of the appointment, you will be charged another \$12.50.

**To schedule a fingerprinting appointment, please follow these instructions:**

1. Visit [www.FieldprintOregon.com](http://www.FieldprintOregon.com)
2. Click on the "Schedule an Appointment" button.
3. Enter an email address under "New Users/Sign Up" and click the "Sign Up" button. Follow the instructions for creating a Password and Security Question and then click "Sign Up and Continue."
4. Enter the Fieldprint Code: **FPontarioSD8**
5. Enter the contact and demographic information required by the FBI and schedule a fingerprint appointment at the location of your choosing.
6. At the end of the process, print the Confirmation Page. **Take the Confirmation Page and two forms of identification with you to your fingerprint appointment.**
7. If you have any questions or problems, you may contact the Fieldprint customer service team.

PHONE: 877-614-4364

EMAIL: [customerservice@fieldprint.com](mailto:customerservice@fieldprint.com)